Serial No.	Particulars of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	
6	Burnt stone slabs 4" thick roughly dressed and fixed.	S.ft.	74		
7	Honne or matti battened doors with frame hinges, bolts, etc., complete.	,,	108		
8	Honne or matti wood battened windows with frame, iron bars, hinges, screws, etc., complete.	,,	9		
9	Honnewood or matti battened ventilators with frame iron bars with swaying arrangements, cotton rope, etc., complete.	,,	13		
10	Chunam plastering two coats	Sqr.	24·00		
11	Nandi or matti wood wrought and put up including wood oiling.	C.ft.	62·82		
12	Roofing with 1st Class Mangalore tiles in teak reepers 1" x 1½".	Sqr.	11·46		
13	Mangalore ridge tiles set in mortar and cement pointed.	R.ft.	89		
14	Flooring with 1st Class Mangalore tiles on 3" concrete bed with cement pointing.	Sqr.	3·53		
15	Flouring with Cudapah slabs 1½" thick on 3" concrete bed including cement pointing.	,,	1·03		
16	Burnt stone pillars nicely dressed ...	S.ft.	32		
17	Cutting grooves in pillars	No.	4		
18	White washing two coats	Sqr.	22·69		
19	Chunam pointing	,,	1·67		
20	Providing wall shelves on pegs with jungle wood planks.	S.ft.	12		
21	Providing links	No.	1		
22	Providing mortar and pestle	,,	1		
23	Painting doors with chocolate painting two coats and wood oiling inside.	Sqr.	3·11	5·00	
24	Constructing latrine complete	L. S.			
25	Tarring to wood-work	L. S. Sqr.	5·00		
26	Clearing site and levelling ground ...	Lump sum			
27	Coping over with compound wall with plastering, complete.	R.ft.	22		
28	Honney wood eave board including chocolate painting.	,,	61		

L. A. H. WINCKLER,
Executive Engineer.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Abstract Notification.

Attention of the public is invited to the detailed Notification dated the 20th November 1930, calling for tenders for constructing the Staff Quarters at Mysore published in Part VI, page 1456 to 1458 of the *Mysore Gazette*, dated 4th December 1930.

The latest date for receiving tenders is 2 P.M., on 15th December 1930.

C. M. CARIAPPA,
Chief Electrical Engineer.